

Scott County Purchasing Division

Specification

Smoking Shelters

December 23, 2003

The bid deadline will be 1/15/04 at 2:00 p.m. Bids are to be sealed and returned to; Scott County Purchasing Division, 428 Western Avenue, Davenport, IA 52801-1004. The outer envelope is to be marked, "Bid on Smoking Shelters."

Questions pertaining to this bid request should be directed to Dave Donovan, (563) 326-8228. No late bids will be accepted.

1. Quantity and Sizes – Purchase of multiple units in the following “approximate” sizes and quantities:

<u>QTY</u>	<u>APPROX. SIZE</u>
2	7' x 10'
2	7' x 14'
1	7' x 16'
1	5' x 7'

Indicate the closest “standard” size available to meet the approximate size and square footage of each unit listed above.

2. Roof System - Roof shall be translucent bubble type, capable of carrying snow load typical of upper Midwest region. Roof shall be self draining with gutter or other mechanism to direct water away from entrances and to prevent water intrusion.
3. Wall System - Sidewalls shall be constructed of anodized (dark bronze) aluminum frame members with synthetic (Lexan™, Plexiglas™, or equivalent material.) glazing panels. Glazing shall be medium tinted for solar filtering to the interior of the enclosure. Sidewalls shall provide ventilation space (2”-6”) at top, bottom or both for “flow through” ventilation. All units shall be four sided with one door opening.
4. Doors – Provide one door per enclosure. Doors shall be aluminum construction matching the appearance of the enclosure. Self closing and damping shall be provided. Doors shall be sturdy construction capable of withstanding normal wind events. Door shall provide cylinder type locking device to allow the enclosure to be secured after hours.
5. Shipping – FOB Destination. Include full shipping cost in bid. Shipping address:

Scott County Warehouse
Attn: Facility and Support Services
4715 North Tremont Avenue
Davenport, IA 52807

24 hour notice required prior to delivery. Fork lift available for tailgate delivery. Ship units modular, knocked down. Protect product appropriately during shipping.

6. Enclosure Installation – Installation by owner. Provide full instructions and modular construction for ease of on-site installation by skilled facility staff. Owner to provide concrete slabs/pad to carry the enclosure. Bolted to concrete by owner. If other installation requirements are necessary, please indicate.