

NOTICE TO BIDDERS

Sealed bids will be received at the Scott County Engineer's Office, 950 E. Blackhawk Trail, Eldridge, Iowa, 52748 until 9:00 A.M., June 12, 2023, for the construction of a bridge replacement project. Project LFM-723—7X-82 is on Z30 (240th Ave) approximately 0.4 miles north of F45 (240th St).

LFM-723—7X-82

110' x 30' CCS Bridge

Item	Description	Quantity	Units
1	EXCAVATION, CL 10, RDWY+BORROW	218	CY
2	EXCAVATION, CL 10, CHANNEL	525	CY
3	MODIFIED SUBBASE	93	CY
4	GRANULAR SHOULDERS, TYPE B	218	TON
5	BRIDGE APPROACH PAVEMENT, AS PER PLAN	245	SY
6	STD OR SLIP FORM PCC PAVEMENT, CLASS C, CLASS 3 DURAB., 8 INCH	774	SY
7	REMOVAL OF EXISTING BRIDGE	1	LS
8	EXCAVATION, CLASS 20	61.0	CY
9	STRUCTURAL CONCRETE (BRIDGE)	263.4	CY
10	REINFORCING STEEL, EPOXY COATED	67,114	LB
11	CONCRETE OPEN RAILING, TL-4	242.9	LF
12	PILE, STEEL, HP 10X42	660	LF
13	PILE, STEEL, HP 12X53	1400	LF
14	CONCRETE ENCASEMENT OF STEEL H PILES, HP 12 X 53 (P10L TYPE 3)	420	LF
15	SUBDRAIN OUTLET, DR-305	3	EACH
16	REMOVAL OF STEEL BEAM GUARDRAIL	482	LF
17	STEEL BEAM GUARDRAIL BARRIER TRANS SECTION, BA-201	4	EACH
18	STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4	EACH
19	STEEL BEAM GUARDRAIL, TANGENT END TERMINAL, BA-225	4	EACH
20	ENGINEER FABRIC	632.0	SY
21	REVETMENT, CLASS E	512	TON
22	REMOVAL OF PAVEMENT	925.0	SY
23	PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	11.8	STA
24	SAFETY CLOSURE	2	EACH
25	TRAFFIC CONTROL	1	LS
26	MOBILIZATION	1	LS
27	MULCHING	0.40	ACRE
28	NATIVE GRASS SEEDING	0.40	ACRE
29	SILT FENCE	260.00	LF
30	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	65.00	LF
31	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 INCH DIAM.	130	LF

Late Start Date – May 1, 2024

Working Days - 70

Prospective bidders must be on the Iowa Department of Transportation's current list of Qualified Bidders. Plans, bidder documents and information may be obtained from the Scott County Engineer's Office, 950 E. Blackhawk Trail, Eldridge, Iowa, 563-326-8640.

Elliott Pennock, EIT
Assistant Scott County Engineer